



ON-GRADE PRECAST CHAIN WALL FOUNDATION

PRODUCTS



GROUNDING IN STRENGTH

Functional shelters in one day.

Forterra's chain wall foundation provides a structurally sound, on-grade or elevated foundation to support your prefabricated shelter or equipment building. This patented design expedites installation and can avoid potential time delays due to weather, quality control issues in the field and additional costs associated with cast-in-place solutions. The on-grade foundation can be custom made to fit various shelter sizes and delivered anywhere in the continental United States. Because the chain wall arrives at the job site ready to be installed, the site preparation does not involve concrete forms, pouring concrete, curing times and is not reliant on weather. Your shelter is functional in record time.

The Forterra Advantage

Forterra's Precast Chain Wall Foundations affords the following advantages:

- One crane installs both the chain wall and shelter
- Virtually no weather delays
- Expedites inspection and permit process
- Delivered to your site as a finished foundation
- Eliminates the need for forms, concrete pours and curing time
- Minimal site preparation
- Minimal labor required
- Higher quality control
- Single day installation
- Delivered anywhere in the U.S.
- Custom made to fit various shelter sizes

Sizes

- L=20ft, W=11.5ft, H=6in to 7ft above ground level or stackable to 20ft AGL
- Accommodates standard buildings 16ft, 20ft and 28ft
- Custom sizes available

Industries

- Telecommunications
- Oil and natural gas
- Public utilities
- Transportation
- Land mobile radio

The Shape of Value

By combining the efficiency of precast materials and the durability of concrete, not only can projects be finished in less time, at lower cost, with minimal downtime, but they're also built to withstand the demands of time and pressure.

